



October 22, 2026

The City of Darien is soliciting for competitive quotes for Ditch Maintenance Restoration. The goal is to maintain positive sheet flow of storm water through open ditches.

The vendor shall have the ability to set flow grades from 1.5 to 2.5 %. The scope of work will be determined by the Superintendent. The work areas will consist of identified areas ranging from 10-150 feet long by 5 to 20 feet in width. The work will further include adjusting storm inlets and 12x12 garden inlets located in the right of way. Adjustments will consist of removing/adding concrete adjusting rings ranging from 1-6 inches and replacing/adjusting 12x12 inlets/grates to grade. The scope of work includes:

Mechanical Grading - depths of up to 6 inches

Mechanical Rototilling - depths of up to 4 inches

Grading of topsoil - depths of 3 to 6 inches

Sod Preparation & Starter Fertilizer - adding up to two inches of top soil & supplying sod & starter fertilizer -10-10-10 fertilizer

Seed & Straw Mat & Starter Fertilizer-Vendor to supply seed & straw mat & starter fertilizer-10-10-10 fertilizer

Storm Sewer - Inlet Adjustments 1-6 inches

12 x 12 Garden Inlets - Adjustment

12 x 12 Garden Inlet remove & replacement - limited

The attached summary sheet is compiled on unit pricing per the above scope of work and must be used. The work will be awarded on a Total Cost basis. The City will provide topsoil, aggregate, and all storm sewer materials. The City will be responsible for watering all restorations. The City of Darien reserves the right to reduce, eliminate, or increase the specified material and/or quantity. The pricing shall be held in place from May 1, 2027 through April 30, 2028. Additionally, the City will also be entertaining 2 optional extensions: May 1, 2028 through April 30, 2029 and May 1, 2029 through April 30, 2030. The projects will be completed on a city block length at various locations throughout the year.

Quotes will be accepted until November 12, 2026, until the hour of 9:30 a.m. Quotes may be emailed to rkokkinis@darienil.gov followed by an original copy delivered to the City of Darien at 1702 Plainfield Road and clearly marked as Ditch Maintenance Restoration, ATTN: Municipal Services.

Prevailing wage rates apply. Certified payroll shall be submitted with payout request.

Any and all requests or addendums shall be made in writing to the attention of Director of Municipal Services via dgombac@darienil.gov. All requests will be responded to within 48 hours to all bidders on file.

DITCH MAINTENANCE RESTORATION SERVICES QUOTE REQUEST

2027 DITCH MAINTENANCE RESTORATION SERVICES						2027 - 2028		2028 - 2029		2029 - 2030	
DESCRIPTION	MINIMAL QUANTITY- RANGE	MAXIMUM QUANTITY- RANGE	UNIT	ESTIMATED QUANTITIES	MULTIPLIER QUANTITY	UNIT PRICE	TOTAL COST	UNIT PRICE	TOTAL COST	UNIT PRICE	TOTAL COST
EXAMPLE "A"	1	220	SQUARE YARD	N/A	220	\$ 1.00	\$ 220.00	\$ 1.05	\$ 231.00	\$ 1.10	\$ 254.10
A. LABOR COST FOR GRADING-MECHANICAL GRADING/ROTTILLING, PREPARATION AND PLACEMENT OF TOPSOIL FROM 1-6 INCHES EXCAVATIONS TO BE DISPOSED OF BY THE CITY - THE CITY WILL PROVIDE TOPSOIL	1	200	SQUARE YARD	200	200						
B. LABOR COST FOR ADJUSTING STORM SEWER INLETS 1-6 INCHES. REMOVED CONCRETE RINGS SHALL BE RETURNED TO THE PUBLIC WORKS FACILITY.	1	100	EACH	100	450						
C. LABOR COST FOR ADJUSTING 12 X12 GARDEN INLETS 1-6 INCHES.	1	100	EACH	100	450						
D. LABOR COST FOR REMOVING AND REPLACING 12 X12 GARDEN INLETS 12-18 INCHES.	1	100	EACH	100	450						
E. SOD-RESTORATION-INCLUDES FERTILIZER, SOD AND PLACEMENT-CITY WILL BE RESPONSIBLE FOR WATERING	100	4,000	SQUARE YARD	5100	5,100						
F. SEED-RESTORATION-INCLUDES FERTILIZER, SEED, STRAW BLANKET AND PLACEMENT-CITY WILL BE RESPONSIBLE FOR WATERING	100	4,000	SQUARE YARD	5100	5,100						
TOTAL COSTS A+B+C+D+E+F											
Company Name:											
Address:											
Submitted By:											
Date:											
Telephone Number:											
Mobile Telephone Number:											
Fax Number:											
E-mail Address:											
Authorized Signature:											